

BID SCHEDULE

**Mosher Springs Waterline Improvement Project, Phase 2
May 15, 2018**

Item No.	Estimated Quantity	Unit	Description and Unit Price in Words	Unit Price	Total Price
1	1	L.S.	Mobilization, including any and all equipment necessary to complete project, (this item amount can not exceed 5 percent of total bid), per lump sum.		
			(Lump Sum Price - Words)		
2	8,000	L.F.	10" D.I.P., Class 50 Raw water line from upper 10" tee in Gypsum Creek Road, to lower 8" tee in Gyp. Ck. Rd.above doghouse, including excavation, bedding, backfill, compaction, tees, fittings, joint restraints, bends, polyethylene wrap, tracer wire, complete and in place, per lineal foot.		
			(Unit Price - Words)		
3	2	Each	8" Gate Valve with valve box and appurtenances, complete and in place, per each.		
			(Unit Price - Words)		
4	3	Each	10" In-line Gate Valve with valve box and appurtenances, complete and in place, per each.		
			(Unit Price - Words)		
5	2	Each	Construct and install air/vac valve vault, including excavation and backfill, precast concrete vault, valves and fittings, complete and in place, per each.		
			(Unit Price - Words)		
6	1	L.S.	Restoration of work areas, final grading, revegetation.		
			(Lump Sum Price - Words)		
7	1	L.S.	Erosion control and silt fencing, complete.		
			(Lump Sum Price - Words)		

BID SCHEDULE

**Mosher Springs Waterline Improvement Project, Phase 2
May 15, 2018**

Item No.	Estimated Quantity	Unit	Description and Unit Price in Words	Unit Price	Total Price
8	4,000	TON	Purchase and deliver "virgin 3/4 spec base from Gypsum Pit" on County Road as required by Eagle County, NOT including grading, compaction or mag chloride, in place, per ton.		
			(Unit Price - Words)		
9	1,000	C.Y.	Import of select backfill material if required, including placing and compacting, complete in place, per cubic yard.		
			(Unit Price - Words)		
10	1	L.S.	Provide traffic control and traffic control plan acceptable to Eagle County and Town of Gypsum in conjunction with Eagle County Permit to Construct in Public Way, complete.		
			(Lump Sum Price - Words)		
11	1	L.S.	Connection to existing 10" DIP line at upper end of new 10" DIP line, complete and in place.		
			(Lump Sum Price - Words)		
12	1	L.S.	Connection at lower end of new 10" line (to existing 8"). Replace existing 6 x 6 tee with 10 x 10 tee and extensions and reducers as needed to connect to existing 8" DIP and 6" PVC pipes. Also includes installation of PVC conduits as described in Addendum #1, Item 5.		
			(Lump Sum Price - Words)		
TOTAL ALL TWELVE ITEMS ABOVE:					_____

BID SCHEDULE

**Mosher Springs Waterline Improvement Project, Phase 2
May 15, 2018**

Item No.	Estimated Quantity	Unit	Description and Unit Price in Words	Unit Price	Total Price
BID ALTERNATE ONE: 12" HDPE					
1a	8,000	L.F.	12", DR7, DIPS, PE4710 HDPE Raw water line from upper tee to lower tee, including excavation, connection to existing, bedding, backfill, compaction, fittings, joint restraints, bends, tracer wire, complete and in place, per lineal foot.		
(Unit Price - Words)					
2a	3	Each	12" In-line Gate Valve with valve box, transition fittings and appurtenances, complete and in place, per each.		
(Unit Price - Words)					
3a	1	L.S.	Connection at lower end of new 12" line (to existing 8"). Replace existing 6 x 6 tee with 12 x 12 tee and extensions and reducers as needed to connect to existing 8" DIP and 6" PVC pipes.		
(Lump Sum Price - Words)					
4a	1	L.S.	Connection to existing 10" DIP line at upper end of new 12" HDPE line, complete and in place.		
(Lump Sum Price - Words)					

BID SCHEDULE

**Mosher Springs Waterline Improvement Project, Phase 2
May 15, 2018**

Item No.	Estimated Quantity	Unit	Description and Unit Price in Words	Unit Price	Total Price
BID ALTERNATE TWO: C900, DR 14, PVC					
1b	8,000	L.F.	10", DR14, C900 PVC Raw water line from upper tee to lower tee, including excavation, connection to existing, bedding, backfill, compaction, fittings, joint restraints, bends, tracer wire, complete and in place, per lineal foot.		
(Unit Price - Words)					
2b	3	Each	10" In-line Gate Valve with valve box, transition fittings and appurtenances, complete and in place, per each.		
(Unit Price - Words)					
3b	1	L.S.	Connection at lower end of new 10" line (to existing 8"). Replace existing 6 x 6 tee with 10 x 10 tee and extensions and reducers as needed to connect to existing 8" DIP and 6" PVC pipes.		
(Lump Sum Price - Words)					
4b	1	L.S.	Connection to existing 10" DIP line at upper end of new 10" PVC line, complete and in place.		
(Lump Sum Price - Words)					